HASSAN DIVISION.

Dated 15th November 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 30th November 1929, for constructing a mosque at Channarayapatna, Hassan District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a mosque at Channarayapatna, Hassan District", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for the Renovation of the Mosque at Channarayapatna.

Sl. No.	Items of work	Per	Quantity
1	Earthwork excavation foundation	C.yd.	32
2	Size stone in chunam	C.ft.	1,189
3	Superstructure, burnt brick in mortar	„	1,652
4	Rolled steel girders including lifting and fixing	Cwt.	17·4
5	Teakwood work wrought and put up	C.ft.	51·90
6	Pucca terrace 9″ thick	Sqr.	5·53
7	Teakwood doors battened with fastenings, etc., complete ...	S.ft.	84
8	Do do windows with battened shutters, iron bars., etc.	„	48
9	Do do shelves do complete ...	„	24
10	Cornice dental 9″ thick	R.ft.	122
11	Ornamental parapet wall over terrace	„	91
12	Do doom with finials, etc., complete	Each	1
13	Masonry ornamental finials over parapet	„	14
14	Chunam mortar plastering and smoothening	Sqr.	24·58
15	Pointing with cement	„	2 26
16	Flooring with 3″ concrete and chunam mortar plastering over ..	„	2·28
17	Do 1st Class Mangalore squre tiles on 3″ concrete with cement pointing.	„	4·06
18	Tarring the portions of wood	L. S.	...
19	Chacolate painting to windows	Sqr.	1·20
20	Wood oiling 2 coats	„	6·60
21	White washing 2 coats	„	24·58
22	Dismantling the existing buildings and levelling the ground ...	Lump	sum Rs.
23	Burnt stone slab 6″ thick dressed	S.ft.	225
24	Do brick in mortar arch work	C.ft.	8

N. KRISHNA IYENGAR,
Executive Engineer.

6 D

KADUR DIVISION.

Dated 31st May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 28th November 1929, till 3 P.M., for raising the waste weir crest of Indavara-Huligunda Tank. Reg. No. 203 of Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for raising the waste weir of Indavara-Huligunda Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10. No claims for enhanced rates, will be entertained on any account after the acceptance of tenders.

11. Rates should be quoted for each item of work and lumpsum rates are subject to modification as per data worked out during execution.

Detailed estimate for raising the waste weir of Indavara-Huligunda Tank, Chikmagalur Taluk, Registered No. 203, Major Tank.

Particulars of work	Quantity	Per	Rate	
			In figures	In words
1. Earthwork to bund watering and tamping ...	7,502	C.yd.		
(*a*) Do above, saturation line 2′ high in rear of bund.	11,356	,,		
2. Cutting grips in bund	4,501	S.yd.		
3. New stone work with jelly backing and wedging	112	C.yd.		
4. Jungle clearing, removing roots, etc. ...	L. S.	...		
5. Removing and refixing, Grade, Index, Register No. and B. M. Stones.	10	No.		
Waste Weir R. L. 103·00, *Length* 42, *Crest width* 3 *feet.*				
1. Earthwork excavation chargeable to bund ...	..	...		
2. Concrete stone jelly in mortar	189	C.ft.		
3. Burnt brick in surki mortar	1,630	,,		
4. Plastering with surki mortar	11·39	Sqr.		
5. Removing, cutting and refixing old burnt stone slab in surki mortar.	326	S.ft.		
6. Burnt stone slabs new to body wall set in surki mortar.	14	,,		
7. Cement pointing to coping slabs	3·40	Sqr.		
8. Unforeseen items	L. S.	...		

L. A. H. WINCKLER,
Executive Engineer.